

**Addendum No. 1**  
**Rood Street Pavement and Drainage Improvements**  
**City of Northwood**  
**March 10, 2008**  
**Bid Date: March 14, 2008**

**Construction Drawing:**

1. On Sheet 3 of 6, change the existing stone driveway detail by eliminating the Item 448-3" Asphalt Concrete. The existing stone driveways shall be replaced with only Item 304-6" Aggregate Base.

**Construction Drawing / Contract Documents:**

1. To help determine the contingency amounts for each item listed in the General Summary on Sheet 2 of 6 of the construction drawings and in the Bid Schedule on Pages 00300-4 and 00300-5 of the contract documents, the following table is presented:

<b>Description</b>		<b>Contingency Amount</b>	
202	Structure Removed	1	EA
202	6" to 15" Pipe Removed	121	FT
254	Pavement Planing, Asphalt Concrete	225	SY
408	Prime Coat	91	GAL
448	Asphalt Concrete, Surface Course, Type 1, PG 64-22	9	CY
448	Asphalt Concrete, Intermediate Course, Type 1, PG 64-22	12	CY
SPEC	Base Improvement	250	SY
603	4" Conduit, Type E	100	FT
603	6" Conduit, Type E	100	FT
603	6" Conduit, Type B	25	FT
603	6" Conduit, Type C	25	FT
603	Sanitary Conduit, Type B	165	FT
603	10" Conduit, Type B	25	FT
603	12" Conduit, Type B	50	FT
603	12" Conduit, Type C	50	FT
604	Catch Basin Modified, 2-2B, As Per Plan	2	EA
638	Copper Service, Type K	100	FT