

ADDENDUM NUMBER ONE  
SOUTH COMPASS DRIVE PHASE 2  
PROJECT NO. 10E06101  
June 6, 2008  
BID OPENING: June 12, 2008 at 10:00 am

PLAN SET

Sheet 1 of 9

Removed the standard drawing for an A-2 catch basin from the Wood County Standard drawing list. Added the Lucas County standard drawing for an A-2 catch basin. The A-2 catch basins shall be constructed per the Lucas County standard drawing.

Sheet 3 of 9

Modified several quantities as follows:

8" conduit, Type B from 129 to 136

12" conduit, Type C from 74 to 82

30" conduit, Type C, 706.02 w/ 706.11 joints from 822 to 827

42" conduit, Type C, 706.02 w/ 706.11 joints from 392 to 391

H-2 Manhole from 6 to 7

Sheet 5 of 9

The storm sewer was relocated behind the multi-use path. This will eliminate the need for premium backfill where the storm sewer was under the multi-use path. MH #15 was added. The quantities on the plans and in the bid documents were changed accordingly.

Sheets 6 of 9

The cross-sections were updated to reflect the change in the storm sewer system.

Sheet 7 of 9

The cross-sections were updated to reflect the change in the storm sewer system.

BID DOCUMENTS

Section 00300-9 & 00300-10 – The quantity for Item #21 changed from 129 to 136. The quantity for Item #26 changed from 74 to 82. The quantity for Item # 28 changed from 822 to 827. The quantity for Item #29 changed from 392 to 391. The quantity for Item #46 changed from 157 to 495. The quantity for Item #47 changed from 485 to 157.

Section 01500-13 – Item 4.03 B shall be changed to read “The project surveying layout work described in 1.02 C 2 will be provided by the *Owner*”.